


Tender Document



Project: CLINK BEDS

05 TECHNICAL PRELIMS

DRAFT

Date 04.05.26

Author S. Jaensch / A. Alzeyat

For **CLINK**
HOSTELS

General Contract and Technical Preliminaries Interior fittings

Tenders to be sent in by email only to the following person:

Stefanie Jaensch
Stefanie Jaensch INTERIOR DESIGNS - Interior Designer -
E-Mail: SJ @stefaniejaensch.de

Ahmed Al Zeyat
Contact Project Lead
E-mail I AZ@stefaniejaensch.de
www.stefaniejaensch.de

Mark Hogarty
Acquisitons Manager - Clink
E-Mail: mark.hogarty@clinkhostels.com

- 1) It will be at the discretion of the project team whether to consider tenders submitted after this time.
- 2) Tenders will be considered valid for 90 days from date of submission.
- 3) The Contractor is advised of the special nature of this contract where time is of the essence. The Contractor must supply a detailed construction programme as part of his tender indicating proposed completion date for the works. Tenders received with no construction programme may be considered invalid.
- 4) The Contractor shall note that the works shall be carried out as described in the Preliminaries, drawings and specifications.
- 5) The Contractor will indicate in his tender for the best possible delivery date, as this will be taken into account when assessing the tenders.
- 6) The Contractor is required to read carefully each item in all sections of the tender documents and provide a detailed price breakdown and carry the total of all sections to the Summary.
- 7) The Contractor is required to comply with the Safety, Health and Welfare at Work (Construction Amendment) Regulations 2013.
- 8) The Contractor will be appointed as a Domestic Sub-Contractor to the main works contractor.
- 9) The Contractor shall provide a Method Statement for these elements of the works. Tenders received with no method statement for these works may be considered invalid.
- 10) The lowest or any other tenderer may not be appointed to carry out the works.
- 11) Contractors will not be reimbursed for any expense occurred in compiling this tender. Tenders received with none of the above deliverables may be considered invalid. Bond The Contractor must include in his tender for entering into a bond with an approved insurance company for 15% of the value of the contract for the proper completion of the contract works.

Bond

The Contractor must include in his tender for entering into a bond with an approved insurance company for 15% of the value of the contract for the proper completion of the contract works. Kindly acknowledge, by e-mail to contact person named above ,receipt of tender documents and confirmation that your tender will be returned on the due date (TBC)

The following services are to be provided by the contractor free of charge in accordance with the technical preliminary remarks:

A.1 In particular, the following DIN standards are to be taken into account: VDI guideline 2719, gluing according to E11055 (3+4), 4079, 4102 (5), 4108 (Bbl 1+1-5), 4109, 4172, 7748 (1+2), 16926, 16935, 17611, 17615 (1-3), 18045, 18056, 18095 (1), 18545 (1+3), 68121 (1+2), 68122, 68123, 68126 (1+3), 68360 (1+2), 68705 (2-4), 68706 (1+3), 68750, 68754 (1), 68761 (1+4), 68765, 68800 (1-5), 18101, 18103, 18201, 18202, 18203, 18299, 18330, 18334, 18353,18354,18356, 18355, 18357, 18360, 18361, 18363, for electrical work/luminaires: in accordance with VDE and DIN 183382 guidelines, Euronorm, as well as ENEC guidelines, workplace guidelines, accident prevention regulations, official decrees, recognised rules of technology.

A.2 A fire protection report is available and must be complied with unless any deviations are expressly agreed in writing with the fire protection expert and the Client.If the use of materials of fire protection class A is required, the resulting furniture weights, in particular for doors and flaps, shall be agreed with the interior designer prior to manufacture.As a matter of principle, "easily flammable" materials must not be used under any circumstances.Drill holes and openings must be made in accordance with the fire protection regulations.

A.3 All work shall be carried out in accordance with the regulations of the employers' liability insurance associations. All necessary protective measures must be taken and protective clothing worn.

B.1 All dimensions and connections required for the installation are to be checked on site on one's own responsibility; deviations are to be agreed with the interior designer prior to manufacture.If, due to the progress of the construction work on site, it is not or only partially possible to take measurements on time, binding measurements (for masonry, dry construction, floor construction) shall be determined together with the local construction management of the Client and the General Contractor as well as the Interior Designer, according to which the interior fittings can be produced. In particular, it must be checked whether the angles on the construction site have been adhered to in accordance with the plans - if this is not the case, appropriate compensation must be made in coordination with the interior designer during furniture assembly. Unevenness must be compensated for without additional costs.

B.2 Should unusual total weights occur upon delivery of the items, this must be clarified in advance with the interior architect and the responsible structural engineer and documented to the client.B.3 The Contractor shall clarify on the basis of the plans and on site that the parts to be delivered by him can be transported to and from and delivered without any problems; all auxiliary equipment necessary for this shall be provided by the Contractor. The lifts in the building cannot be used!The contractor shall himself provide lockable storage facilities for the parts to be delivered and any tools etc. Any storage facilities on site must be clarified and agreed in good time with the interior designer and the local site management of the general contractor.

B.4 Before submitting his tender, the contractor is obliged to review and examine the interior designer's plans in coordination with the bill of quantities. In this context, he is also obliged to inform himself on site about the circumstances and conditions under which he is to perform his services; he must point out in detail to the Client and the interior architect in writing any ambiguities, discrepancies and / or gaps in the documents and plans submitted to him before submitting his tender. Mirror-inverted installation solutions shall be checked on the basis of floor overview plans (to be requested in case of doubt).

B.5 The contractor shall prepare assembly drawings (details on a scale of 1:1, 1:5 or 1:20) in good time before the start of production, which shall be submitted to the interior designer in duplicate for approval. The interior designer shall be granted a reasonable inspection period of at least 14 days. The costs for the preparation of these plans shall be included in the unit prices submitted. Submitted plans shall not be valid until they have been approved in writing by the interior designer for execution.Any necessary templates shall be prepared free of charge.

B.6 All installation dimensions and weights as well as necessary inspection flaps and technically required ventilation grilles or ventilation slots for all technical devices to be integrated into the installations are to be coordinated with the interior designer with the involvement of the respective specialised engineers. Adequate ventilation of built-in appliances supplied shall be carried out in accordance with the manufacturer's specifications.

B.7 Delivery and installation including all necessary fasteners are included in the unit prices. Unless otherwise stated, luminaires supplied shall be supplied with (adequately ventilated and arranged in accordance with fire protection regulations) electronic transformer/ballast and light source (both VDE/ENEC approved branded goods) and shall be installed and wired up to the interface with the on-site power supply in consultation with the interior designer and the local specialist engineer. If luminaires are supplied, cable lengths and arrangements of switches as well as the type of light sources to be used must be agreed with the interior designer. The possibility of revision must be ensured in an uncomplicated manner for ongoing operation. All luminaires and switches shall be offered with a cable set up to the transfer point.

B.8 Transport costs, storage costs, insurance, packaging, waste disposal, as well as permit fees, travel and accommodation costs including allowances and overtime are included in the unit prices.

B.9 For all parts supplied, the written documents, in particular the instructions for use, the warranty cards, the care instructions and all test certificates must be handed over to the interior designer without being requested to do so one week before acceptance.

B.10 Immediately after the order has been placed, the tendered surfaces, including applied edges, must be submitted in duplicate as samples to the interior designer for approval free of charge. All upholstery fabrics, curtain fabrics, natural stone, artificial stone, metal and glass surfaces shall also be sampled and submitted to the interior designer free of charge immediately after the order has been placed. Hotel room chairs and armchairs, as well as hotel room lamps, corridor and staircase lamps, conference chairs and restaurant chairs, as well as other furniture at the special request of the Interior Designer shall be sampled free of charge after the order has been placed.

B.11 Wooden surfaces, chipboard or other surfaces and their matching edges and applied mouldings, with solvent-free, UV-resistant water-based varnish or equivalent. Resistant to scratches, alcohol and other liquids according to the latest DIN regulation/standard, matt surface.

B.12 Top-coated surfaces on MDF, if necessary milled with DD varnish or solvent-free, UV-resistant, opaque water-based varnish or similar, resistant to scratches, alcohol and other liquids in accordance with the latest DIN regulations/standards, matt, very scratch-resistant surface.

C.1 All necessary notches, openings or similar, for all built-in and/or add-on parts such as sockets, switches, cable entry sockets, as well as irrigation and/or drainage pipes or components, air-conditioning systems, heaters, pipes, cables, wall projections, on-site plinths, columns etc., are included in the order sum and must be identified and implemented in good time according to construction requirements. The prescribed distance between adjacent drill holes must be observed for the respective connections; e.g. the necessary distance between weak and strong current connections.

C.2 Fixing furniture to the floor is not always possible everywhere due to floor ducts and underfloor heating. If fastening to the floor should be necessary, this may only be done in each individual case in close consultation with the interior architect and the responsible construction management of the GU. The fixing to the wall and/or - as far as possible - floor and/or ceiling is included in the installation price irrespective of the existing or constructed building structure such as e.g. concrete, plastered brickwork, plasterboard stud walls, plasterboard walls and suspended ceilings. If substructures are required on site, these must be arranged by the contractor at his own expense and on time without being requested. As a matter of principle, it must be checked together with the interior architect prior to the construction work whether the places where the furniture is to be fastened have sufficient load-bearing capacity and whether fastening is permitted there at all; in case of doubt, the architects, the technical building services planner as well as the fire protection expert, structural engineer and/or the general contractor must be involved.

C.3 Wall connection pieces and fitting strips are always included in the unit prices. Floor and wall connections are to be provided with permanently elastic jointing after consultation with the interior designer. Colours for this are to be agreed with the interior designer. Connections to wall and ceiling surfaces are to be sealed with acrylate, connections to natural stone and tiles as well as glass, PVC-like coverings and metal coverings with permanently elastic silicone grouting. In principle, fungus-inhibiting silicone material is to be used.

C.4 In the case of mitres, the corresponding panels must always be provided with the corresponding ABS or thick veneer edge before bevelling.

C.5 All elements in contact with the floor must be insulated against rising damp. Elements standing on floors that have to be cleaned with moisture must be protected against moisture penetration by plastic inserts.

C.6 For mini-bar doors, a trailing hinge is to be supplied and installed. Devices to be installed (e.g. minibar, safe, etc.) shall be fitted with fitting panels. Safes shall be firmly anchored in accordance with the regulations.

C.7 If sockets and/or switches are to be installed in wardrobe side-panels, bed headboards, etc., appropriate trim panels are to be produced and installed within the carcase. In particular, the cable routing in the bed headboards (e.g. due to electromagnetic radiation) must be precisely defined with the interior designer (if necessary, with the involvement of the technical building services planner) in good time before the start of work.

C.8 Electrical cables behind furniture fixtures are to be determined exactly with the interior designer (if necessary, with the involvement of the technical building services planner) in good time before the start of work and looped through to the outlet holes in coordination with the interior designer and the electrical company. At the request of the electrical company, these flashings shall be made removable and retractable at any time for installation purposes.

C.9 Cable routing ducts or cavities provided for this purpose must be easy to revise.

C.10 The detailed assembly sequence is to be coordinated with the interior designer and, if necessary, third party trades, in particular the electrician's trades, and the floor layers (plinth!) together before assembly begins.

C.11 Fixing by means of shooting apparatus is not permitted.

C.12 Before drilling, the wall or floor must be checked for cables and pipes at the appropriate points.

C.13 Under no circumstances may the stability be impaired by the installation work. Should cracks or settlements become apparent, the site management shall be notified immediately.

D.1 Only formaldehyde-free flat pressed boards and PCB-free material may be used. This must be verified by a test certificate from a state-recognised institute prior to manufacture.

Only materials with a high level of health and environmental compatibility may be used.

No materials may be used that contain asbestos, CFCs, HCFCs, CFCIs or any other materials that are harmful to health, harmful to the environment or otherwise harmful to the state of the art at the time of use, polluting or otherwise hazardous substances.

D.2 Visible holes/cuts/milled holes must always be edged and / or, in the case of MDF coreboards, painted to cover them.

D.3 Edge coating: with laminate and melamine resin coating, ABS plastic edging strips of identical colour and surface pattern are to be used in 2 mm material thickness.

For natural wood veneered panels, 2 mm thick veneer edges are to be provided for shelves, table tops, drawers, doors and sideboard covers; for other components, veneer edges of min. 0.6 mm thickness are to be provided.

D.4 Horizontal surfaces are generally to be covered with HPL or CPL for plastic surfaces. Vertical surfaces may be produced in direct-coated panels with melamine resin surfaces.

D.5 Lacquered surfaces of wooden parts are to be made of DD lacquer or solvent-free, UV-resistant water-based lacquer or equivalent, scratch-resistant, resistant to alcohol and other liquids in accordance with the latest DIN regulations/standards.

D.6 Cabinet doors and drawer fronts must always be fitted with sound-absorbing, transparent silicone buffers.

D.7 As a matter of principle, all wood fibre boards must be coated on both sides so that warping of the boards is excluded as far as possible. In non-visible parts, this can be done (if not mentioned otherwise in the LV) with counteracting foil.

D.8 In kitchen, buffet, bar and WC areas, as well as in wellness areas, waterproof glued chipboard panels and correspondingly suitable edges must always be used. If dry construction boards are used, appropriate damp room boards must be used.

D.9 All wooden parts must be procured from the best seasoned varieties and be suitable for the respective place of use; furthermore, all edges of the wooden parts must be flawless, without wood defects and knotholes or other defects.

D.10 Veneers are to be used as sliced veneers; the unwinding as a selected grain pattern, veneer direction according to the interior designer's specifications.

D.11 For softwoods, spruce or European softwood is generally to be chosen, unless otherwise described in the tender text.

D.12 Hardwoods must be approved (no rare or tropical woods, unless otherwise described in the specifications) and artificially dried to 7% moisture content. All timbers shall be specifically selected for the particular component based on suitability and shall meet the quality requirements of the sample pieces.

D.13 Chipboard cores shall be first choice and resin and high pressure bonded. Only first choice MDF shall be used. Plastic veneers shall be glued with carbamide resin.

D.14 Furniture shall be constructed in such a way as to ensure adequate rear ventilation between the furniture and the walls. The building moisture must be measured 14 days before installation and again before the installation itself. If the construction is too damp, written concerns must be raised in good time. Concrete, screed and plaster, for example, must not have more than 3% moisture by volume.

D.15 When mitre joints are made, the abutting panels must always be provided with ABS or veneer strong edges before trimming.

E.1 All fittings are to be selected in an all-metal version suitable for the object. Pull-outs are to be low-noise full-extension runners with ball bearings/telescopic full-extension runners with support brake and self-closing mechanism (load according to the intended use described in the specifications - tipping of the furniture is to be avoided when the drawers are pulled out). The drawers must be secured at the end stop with a double notch to prevent them from falling out. Pull-out system with aluminium frames made of 1.5 mm thick aluminium or equivalent. Load capacity up to 250 N under dynamic load, 60,000 openings and closings. Door fittings can be opened up to 100 degrees unless otherwise described in the specifications. For door heights up to 1600mm at least three hinges(over 1600mm up to 2250mm at least 4 hinges), larger dimensions with counter pull fitting.

E.2 Doors with door locks prepared for PZ, door hinges ball-bearing mounted 3-roller hinge, fittings in accordance with DIN standards and the technical regulations at the relevant building.

E.3 All shelves must be held by safety shelf supports and secured against falling out/tipping over and must be freely adjustable within rows of holes in a 30 mm grid. Load capacity of the shelves min. 50kg/sqm. In the case of bottle and book shelves, the shelves must be secured against sagging by additional frames or similar after consultation with the interior designer.

E.4 All screws must always be galvanised, visible screws as decorative screws or concealed, e.g. with an internal Allen key or covered with wooden plugs as specified by the interior designer.

E.5 Movable elements shall be manufactured in such a way that they cannot tilt when moved. Castors shall be suitable for the load, shall not damage the floor covering and shall be equipped with brakes.

F.1 Unless otherwise described in the specifications, the surfaces of the trestle shall be protected against scratching by means of metal profiles.

F.2 Cash drawers shall always be equipped with a common insert for banknotes, coins, etc.

F.3 Mail drawers shall always be supplied with an alphabetical subdivision.

F.4 Invoice drawers must always be supplied with a room numbering subdivision.

F.5 All doors and drawers in the conference area, bar area and reception area shall be supplied with integrated security locks as a matter of principle.

F.6 All bottle shelves in the bar area shall be supplied with a roller blind or sliding doors made of safety glass with integrated locks, depending on the interior designer's specifications.

F.7 Litter bins shall always be extractable and equipped for the use of commercially available bags. Litter bins in the bar and restaurant area as well as in the guest room area shall be non-flammable.

G.1 Unless otherwise described in the specifications, natural and artificial stones shall be slightly rounded (3 mm radius) on all visible surfaces and edges; protruding corners shall be rounded in such a way that there is no risk of injury. Fastening and bonding must be carried out in accordance with the material and manufacturer's instructions. All drillings and cut-outs are included in the unit price. In the buffet area, it must be ensured that the natural stone in the area of cold or heat units has the required temperature suitability. The surfaces shall be provided with sufficient stain protection.

G.2 Glass elements are to be produced in curved form with finely ground edges and bevelled corners on all sides or, in consultation with the interior designer, rounded in vulnerable areas so that there is no risk of injury.

Glass tops on table surfaces are to be provided with clear silicone buffers, unless otherwise described. For overhead or spandrel glazing, laminated safety glass, toughened safety glass or combinations thereof shall be used in accordance with the regulations. Depending on the fire protection requirements, appropriate fire protection glass is to be used. Mirrors made of crystal mirror glass are to be produced with polished edges and with finely ground edges and bevelled corners on all sides; the fastenings for these are to be produced in a fall-proof manner.

Cut-outs and drill holes are included in the price.

G.3 Metal parts are to be supplied with the required protective coating, protective foil, or powder-coated or stove-enamelled. Non-visible metal parts are to be supplied corrosion-protected or hot-dip galvanised. All corners and edges are to be deburred or defused. ce drawers shall always be supplied with a room numbering subdivision.